

JHARKHAND STATE CRICKET ASSOCIATION

INTERNATIONAL STADIUM COMPLEX,
H.E.C. CAMPUS, DHURWA, RANCHI- 834004.

JSCA/RNC/199/342/2023-24

5th October, 2023

Name of Work: Supply and erection of steel structural frame shed including necessary civil work in J.S.C.A. International Stadium Complex, H.E.C., Dhurwa, Ranchi.

INVITATION OF TENDER

Tenders are invited from experienced and bonafide agencies for "Supply and erection of steel structural frame shed including necessary civil work" for all season outdoor practice pitches in J.S.C.A. International Stadium Complex, H.E.C., Dhurwa, Ranchi.

1. SCOPE OF WORK:

- ❖ Relocating existing Green house;
- ❖ Relocating existing water tanks including modification/construction after dismantling of pedestal;
- ❖ Supply, fabrication and erection of M.S. structure of appx size 150'x42'.

2. ELIGIBILITY CRITERIA: -

Bidder must fulfill the following eligibility criteria

2.1. Technical:

1. They should have executed fabrication job of value not less than 15.00 Lakhs (Rupees Fifteen Lakhs only) under single order value during last three years in a reputed organization/Govt. Dept. (list to be furnished alongwith supporting documents)
2. Must possess required technical manpower and equipments for executing the job (list to be furnished alongwith supporting documents).

2.2. Financial:

1. Must have minimum average turnover of Rs.50.00 Lakhs (Rupees Fifty Lakhs only) per year during last three financial years (audited and self-attested copy to be furnished).
2. Must fulfil following statutory requirements:
 - a. PF registration.
 - b. ESIC registration.

3. AUTHORITY OF PERSON SIGNING TENDER DOCUMENT: -

A person signing the tender form or any documents forming part of tender/contract on behalf of the bidder, should be authorized to do so. A letter of Authority should be submitted alongwith tender.

4. EARNEST MONEY: -

EMD of Rs.20,000/- (Rupees Twenty Thousand only) in the form of Demand Draft payable to Jharkhand State Cricket Association at Jamshedpur.

5. PRICE:

The tenderer shall quote as per bill of quantities enclosed at Annexure-1 of the tender. Quoted price shall include, all cost of material labour, transportation, handling, taxes, incidentals, overheads, margin, etc. as applicable excluding GST which shall be added separately in the B.O.Q total

JHARKHAND STATE CRICKET ASSOCIATION

INTERNATIONAL STADIUM COMPLEX,
H.E.C. CAMPUS, DHURWA, RANCHI- 834004.

6. TENDER SUBMISSION:

Tender documents shall be submitted in two parts (packets):-

Part-1 Technical

(Packet-1) shall contain following documents:

- ❖ Covering letter of Tenderer;
- ❖ Credentials that makes bidder eligible;
- ❖ Demand Draft for EMD. of Rs.20,000/- (Rupees Twenty Thousand only);
- ❖ Any clarification tenderer may like to seek.
- ❖ Self-attested documents in support of Techno financial eligibility.

Part-2 Financial

(Packet- 2) **shall contain only the price schedule.**

Packet- 1 shall be opened first. Packet- 2 shall be opened only for those agencies whose all documents including the earnest money are found in order. Bidders shall have no claim for such rejection.

7. PLACE AND DATE OF SUBMISSION OF TENDER:

Bids can be submitted till 04:00 PM on 16.10.2023 in the office of C.E.O. in 1st Floor of Amitabh Choudhary Pavilion at J.S.C.A. International Stadium Complex, Dhurwa, Ranchi.

8. PAYMENT:

- ❖ Amount equivalent to 50% of quoted price for fabricated material brought to site.
- ❖ Balance after completion of work.

9. SECURITY DEPOSIT:

Security deposit shall be deducted from on account bill @5% of the executed value. It will be refunded after successful completion of defect liability period.

10. TIME OF COMPLETION:

The work should be completed within 45 (forty-five) days from the date of issue of LOI.

11. DEFECT LIABILITY PERIOD:

The defect liability period shall be one year from the date of certified completion of work.

12. LIST OF APPROVED MATERIALS: -

- ❖ STEEL STRUCTURE:- TATA, SAIL , JINDAL.
- ❖ FASTENER: - HILTI, FISCHER.

13. ACCOMMODATION:

No accommodation shall be provided for the worker.

14. NO COMPENSATION FOR TENDER SUBMISSION:

Intending tenderers shall submit their tender at their own cost and no compensation shall be payable for expenditure incurred, if any.

JHARKHAND STATE CRICKET ASSOCIATION

INTERNATIONAL STADIUM COMPLEX,
H.E.C. CAMPUS, DHURWA, RANCHI- 834004.

15. FABRICATION:

Fabrication job shall not be allowed inside JSCA premises. However minor fabrication, welding, etc needed during installation/fixing shall be allowed free of charge.

Jharkhand State Cricket Association (JSCA) reserves the right to reject any/all tender without assigning reasons whatsoever.

Tender document can be downloaded from website: www.cricjharkhand.org

For Jharkhand State Cricket Association



(A.K. Singh)
C.E.O.

JHARKHAND STATE CRICKET ASSOCIATION

INTERNATIONAL STADIUM COMPLEX,
H.E.C. CAMPUS, DHURWA, RANCHI- 834004.

PRICE SCHEDULE

S. No.	Work Description	Unit	Qty.	Rate	Amount
1.	Relocation of existing green house by cutting the structure at ground level and shifting to new location including extension of vertical members using new members to retain the same height as was earlier and fixing the same in ground by excavating and jamming the structural members in concrete of 1:2:4 of size 300x300x500mm complete in all respects complete	Lot	1		
2.	Supplying, fabricating and fixing structural steel members for construction of shed using MS circular pipes/hallow tubes, foundation bolts etc as per approved design including two coats of synthetic enamel paint over and including a coat of Zinc primer all complete	Kg	9000		
3.	Relocating existing 2 nos of PVC water tanks including extending the existing one and trimming on the other side /making the new pedestal after dismantling as necessary (Payment for new construction will be made separately) and connecting the existing water lines as per requirement. shall be taken for payment purpose).	Lot	1		
4.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas for foundations, masonry walls etc including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge in all kinds of soil up to 1.5m depth	Cum	60		
5.	Filling available excavated earth (excluding rock) in sides of foundations etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	Cum	40		
6.	Providing and laying in position cement concrete of specified grade below foundations and in flooring including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	13		
7.	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. concrete	Sqm	60		
8.	Providing and laying in position reinforced cement concrete of grade M 25 (1:1:2) (1 cement: 1 coarse sand :2 graded stone aggregate 20mm down nominal size aggregate in foundations, pedestals etc	Cum	12		
9.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level using Thermo-Mechanically Treated bars of grade Fe-500D or more	Kg	900		
10.	Coursed rubble masonry with hard stone (first or second sort) in foundation and superstructure above plinth/ground level Masonry work in cement mortar 1:6 (1 cement :6 coarse sand)	Cum	8		

JHARKHAND STATE CRICKET ASSOCIATION

INTERNATIONAL STADIUM COMPLEX,
H.E.C. CAMPUS, DHURWA, RANCHI- 834004.

11.	Brick work with common burnt clay F.P.S. (non-modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	5		
12.	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design& shape, laid in required colour and pattern over and including 50mmthick compacted bed of coarse sand over 50mm thick concrete, filling the joints with line sand, etc. all complete as per the direction of Engineer-in-charge Payment for concrete will be made separately	Sqm	75		
13.	Half brick masonry with common burnt clay F.P.S. (non-modular) bricks of class designation 7.5 in foundations and plinth in cement mortar 1:4 (1 cement: 4 coarse sand)	Sqm	30		
14.	Cement punning over plastered/concrete surface.	Sqm	50		
TOTAL					
ADD GST					
GRAND TOTAL					

(Rupees in words:

.....)

SIGNATURE OF BIDDER

SEAL